

**QUOTATION FOR THE INTERIOR FURNISHING WORK OF
BANK OF INDIA, VALAKAM BRANCH.**

PART-A

Date:-

Si.No.	Description of work	Qty	Units	Rate	Amount
1	<u>FALSE CEILING (GYPSUM BOARD):-</u> Providing and fixing in position False Ceiling in Gypboard 12 mm thick for horizontals & verticals fixed over G.I frame work as specified by India Gypsum co. Ltd. Including trap doors for A.C unit in 18 mm thick M.R. Grade plywood with Stainless Steel hinges & locks with moulding 1" x 1" for edges including finishing with White Plastic Emulsion Paint etc. Complete in all respects. (Note :-Only the plan area will be measured for payment. No extra payment will be made for cutouts , grooves , mouldings etc. for banking area borders & managers cabin.	800	Sft		
2	<u>FALSE CEILING (ARMSTRONG GRID CEILING):-</u> Providing and fixing in position False Ceiling in Armstrong 600 x 600 mm x 15/16 mm Dune Supreme RH99 Prima tile with Tregular edge framework as specified by Armstrong with suspenders wherever required. Making necessary framework for A.C. ducting, if any, and necessary cutouts for diffusers and light fittings , taping and finishing to proper line & level including making grooves and trap doors for A.C unit in 18mm thick M.R. Grade Plywood with Stainless Steel hinges & Locks with moulding 1"x1" for edges including finishing with White Plastic Emulsion Paint etc. Complete in all respects for banking hall. (Note:- Only the plan area will be measured for payment. No extra payment will be made for cutouts, grooves , moulding etc.)	200	Sft		
3	<u>PAINTING:-</u>				
i)	Providing and applying white plastic emulsion paint of Asian paint/ICI Dulex /Berger and sporty yellow-X 104 shade of Royal luxury Emulsion of Asian paints in minimum 2 coats including scrapping, opening of existing cracks, filling up of 'v' cracks with epoxy expandable putty to required depths making good weak plastered / unplastered surfaces with cement plaster where ever required. Item to include plaster of paris , primer putty & making good existing surface to receive new paint including cleaning on completion of painting work etc. complete in all respects (banking area).	950	Sft		

Si.No.	Description of work	Qty	Units	Rate	Amount
ii)	Painting the secondary areas with white Cement paint without putty. (Inside strong room, pantry, UPS/Electrical room, record room & toilet including ceiling area) of non Banking Area.	2500	Sft		
iii)	Painting the window grills & shutters (Banking Area), with two coats of enamel paint of approved colour.	400	Sft		
4	<u>FACADE OF ENTRANCE DOOR:-</u>	To be done by the Bank			
5	<u>ENTRANCE DOOR:-</u>	To be done by the Bank			
6	<u>FRONT OFFICE COUNTER:-</u> Providing & fixing in position on front office counter 2'6" wide as per drawing no(1-A,1-B,1-C,1-D &15) comprising of the following complete in all respects				
i)	Working top made with 25 mm thick plywood finished with 1mm thick laminate . Outside edge of the working top shall be provided with 1 1/4" x 1" T.W moulding finished with melamine polish. Inside edge will be provided with 1/2" x 1" T.W beading patti with melamine finish.				
ii)	Vetical facia (Apron) made with 18mm thick plywood finished with 1mm thick laminate with 1mm thick groove glazed partition above working top to be provided with				
iii)	Vertical drop (horizontal band) shall be provided on the facia below the working top made with 18 mm thick plywood finished with 1mm thick laminate with provision for consealed light ,1mm thick groove shall be provided at the joint of two different shades of laminate.				
iv)	Glazed partition above working top to be provided with 12 mm thick clear glass cut to the standered shape fixed to partition as per fixing details and to boxing with concealed SS finshed 'D' brackets as shown in the drawing . The exposed edges of the glass shall be finished in mirror polish.				
v)	3' 10" high boxing (10" x 10") made with 18mm thick plywood finished with 1 mm thick laminate including providing and fixing 6mm thick squire frosted glass at a ht. 3'2" above finshed floor level.				
vi)	1'9" high boxing (5"x5") made with 12 mm thick plywood finshed with 1mm thick laminate.				
vii)	Vertical supports made with 18 mm thick plywood finished with white enamel paint.				
viii)	Telescopic CPU Stand / ready made key board tray shall be provided of approved model and make.				
ix)	Foot rest made with T.W member of size 4" x 1 1/2" finished with french polish.				
x)	Drawer units as per drawing shall be provided with multipurpose godrej locks in each drawer. Facia of drawer unit shall be finished with 1 mm thick laminate and all				
	other sides shall be finished with white enamel paint. The				

Si.No.	Description of work	Qty	Units	Rate	Amount
	drawers will be provided with handles (stainless steel finish) and channels as per approval of the project consultant/bank.				
xi)	Boxing as per drawing made with 12mm thick plywood finished with Synthetic enamel paint shall be provided below the table top for electrical conducting and at the bottom for the LAN Cabling / telephone wire conducting. The item to include all necessary hardware and fittings in stainless steel finish, lipping to all edges and making provision only for electrical fitting behind the front. Vertical drop and also in the 10" x 10" boxing as shown in the drawing. Necessary beadings with melamine polish for fixing the glass are to be provided.	22	Rft		
7	<u>CASH COUNTER:-</u> Providing and fixing in position cash counter as per drawing no (2-A ,2-B, 2-C, 2-D, 2-E, 2-F) comprising of the following: i) Working top made with 25 mm thick plywood finished with 1mm thick laminate. Outside edge of the working top shall be provided with 1 1/4" x 1" Teakwood moulding finished with melamine polish. Inside edge will be provided with 1/2" x 1" T. W. beading patti with melamine polish. ii) Vertical facia (Apron) made with 18mm thick plywood finished with 1mm thick laminate with 1 mm thick groove at the joint of laminates of two different shades. iii) Vertical drop (horizontal band) shall be provided on the facia below the working top made with 18 mm thick plywood finished with 1mm thick laminate with provision for concealed light , 1 mm thick groove shall be provided at the joint of two different shades of laminate. iv) Glazed partition of 1' 4" height above working top provided with 12mm thick toughened and frosted glass besides non-transparent film from inside fixed to partition as per fixing details and to boxing with concealed SS finished 'D' brackets as shown in the drawing. The exposed edges of the glass shall be finished in mirror polish. v) Transaction top shall be provided with 12 mm thick toughened glass(partly glazed partly frosted) fixed horizontally with concealed SS 'D' brackets . Both exposed edges (inside & outside) shall be moulded and finished in mirror polish vi) Glazed partition having ht. 1' 0" above the transaction top (in facia) shall be provided with 12mm thick glass(Clear)with cutout of 8" x4" as per drawing.The edges of cutout and top edge of glass are to be mirror polished and to be fixed to the partition as per fixing details and to boxing with concealed				
	SS finished 'D' bracket as shown in glass (clear).Above the slit				

Si.No.	Description of work	Qty	Units	Rate	Amount
	of 4" shall be provided with 12mm thick glass (clear)of 1'6" to be fixed to partition as per fixing details and to boxing with concealed SS finished 'D' brackets as shown in the drawing. The exposed edges shall be finished in mirror polish.				
vii)	7'-7" high boxing (10"x 10")made with 18mm thick plywood as per drawing with 1' 6" horizontal extension at top including providing and fixing 6 mm thick square frosted glass at ht. of 5'11" above finished floor level.				
viii)	1'9" high boxing (5" x 5")made with 12 mm thick plywood finished with 1mm thick laminate are to be provided.				
ix)	Telescopic CPU Stand / Ready made Key board tray shall be provided of approved model and make.				
x)	Foot rest made with T.W member of size of size 4" x 1 1/2" finished with french polish.				
xi)	Drawer unit as per drawing shall be provided and each drawer should have vertical partitions for keeping the correny notes and multipurpose Godrej locks. Facia of drawer unit shall be finished with 1 mm thick laminate and all other sides shall be finished with white enamel paint. The drawers will be provided with handles (Stainless steel finish) and channels as per the approval of the project consultant/ Bank.				
xii)	Boxing as per drawing made with 12mm thick plywood finished with syenthetic enamel paint shall be provided below the table top for electrical conduting and at the bottom for the LAN cabling / Telephone wire conduting. The item to include all the necessary hardware and fittings in SS Finish,lipping to all edges and making provision only for electrical fitting behind the vertical drop and also in the 10" x 10" boxing as shown in the drawing. Necessary beadings with matching melamine polish , for fixing the glass are to be provided as per drawing / as directed.	6	Rft		
8	<u>WICKET GATE:-</u> Double skin partition with Teak wood frame work of size 2" x 2" at a distance of 2'x2' c/c with 6mm marine plywood on both sides finished with 1mm lamination of approved colour counter design With TW Beading all aroundwith melamine finish.It include tower bolts , Hinges,Stopper etc..	10	Sft		
9	<u>FULLY GLAZED FULL HT. PARTITION (FRONTSIDE OF MANAGER'S CABIN)</u> Providing and fixing inposition partly glazed full ht.partition work as shown in the drawing nos (3) & (4) including door as shown in the drawing no. (13) in frame work at 2' x 2' grid (horizontally and vertically) comprising of 2" x1 1/2" T.W sections and /or as per frame work shown in the drawings with 6mm plywood on both sides finished				

Si.No.	Description of work	Qty	Units	Rate	Amount
	with 1 mm thick laminates of approved shade & colour as shown in the drawings. Item to include 8 mm thick glass with etching & frosting as per design and 2" x 2" T.W. member for door sides and glass sides and T.W door frame to take 8 mm thick glass with etching and frosting. All exposed T.W surfaces to be finished in melamine polish of matching laminate colour as directed including all necessary SS finish fittings / Hardware , door closers , Godrej locks and wood preservative paint etc. as per list of approved material and as approved by the Project Consultant / Bank complete in all respects. (Note : In case of false ceiling , the vertical T.W. members to be fixed with pucca ceiling but the area of the Partition payable will be below the false ceiling only). Including one no. of door of size :- 3' x 7' for front side.	95	Sft		
10	<u>PARTLY GLAZED PARTITION FOR CASH CABIN & ONE SIDE OF MANAGER'S CABIN</u> Providing and fixing in position 7' 7" high partly glazed partition for Cash cabins as per drawing Nos (2-A, 2-B, 2-C 2-D & 2-E) including door drawing No. (12) in framework at 2' x 2' grid (horizontally & Vertically) comprising of 2" x 1 1/2 " TW section and /or as per frame work shown in the drawings with 6 mm P lywood on both sides finished with 1mm thick laminate of approved shade & colour as shown in drawings. Item to include 8 mm thick glass with etching and frosting as per design and 2" x 2" TW member for door sides and glass sides and TW door frame to take 8 mm thick glass with etching & frosting .Door size: 2'6" x 7' x 2 No. The door will be provided with TW Louvers finished in melamine polish of matching laminate colour. The doors are also to be provided with Godrej night latch. One wooden tray is also to be provided as per drawing .Necessary cutouts are to be provided in the glass and the edges of the glass cut-outs are to be finished in mirror polish.All exposed TW surfaces to be finished in melamine polish of matching laminate colour as directed including all necessary SS finished fittings/ hardware door closers, Godrej locks, andwood preservative paint etc as per list of approved material complete in all respects.	195	Sft		
11	<u>FULLY BLOCKED FULL HEIGHT DRYWALL GYPSUM BOARD PARTITION (ELECTRICAL, PANTRY & RECORD ROOM PARTITIONS) :-</u> Providing & fixing full height Dry wall partitions using single layer of 12 mm thick tapered edge Gypboard on either sides screw fixed to light weight cold rolled metal sections as per Companys specifications. .				

Si.No.	Description of work	Qty	Units	Rate	Amount
	Also provide two coats of plastic emulsion paint after tapering & puttying the joints and edges. Also provide partly glazed doors with white powder coated frame, 12 mm thick novapan , & 6 mm thick glass. The door to be fixed with hinges, door closer handle & lock as per the specification.	580	Sft		
12	<u>MANAGER'S TABLE (including side credenza)</u> Providing and fixing in position Manager's table of as per drawing no (6) /Officer's table of size 4'6"x2'3" as per drawing no (5) including side storage (credenza) by using 25 mm thick plywood for top and 18mm thick Ply wood for all other horizontal and vertical members. Telescopic CPU stand /Ready made Keyboard tray shall be provided of approved model and make . Footrest made with the TW member of size 4" x1 1/2 " finished with french Polish. Side storage(Credenza) as per drawing shall be provided. Facia of side storage (Credenza) shall be finished with 1mm thick laminate as shown in the drawing and all other sides shall be finished with white enamel paint. The side storage (credenza) shall be provided with handles (SS finish) and channels as per approval of the Project Consultant/Bank. All exposed Plywood surfaces to be finished with 1mm thick laminate of approved make and shade and all exposed edges of table top and ply verticals to have 1" x1/4" TW lipping. All exposed TW sections to be melamined and internal surfaces to have white enamel paint as directed. Item to include Plywood boxing, all necessary hardware and fittings in SS finish, lipping to all edges etc complete in all respects.	1	No		
13	<u>OFFICER'S TABLE (Including side credenza)</u> Material & finish same as manager's table.Size :- 5'0" x 2'0"	1	No		
14	<u>PANTRY COUNTER:-</u> Made of 20 mm edge polished jet black granite on top of the counter pasted on 19mm BWR grade plywood with necessary intermediate support as legs with19mm BWR grade plywood and foot rest made of hardwood. All inside portions finished with primer & 2 coats of enamel paint of approved colour. All exposible edges finished with white beechwood lipping of melamine clear glossy finish as per design. Size:- 7' 0" x2' 0" depth x 2' 6" Ht.	8	RFT		
15	<u>LOW HEIGHT STORAGE (MANAGER'S CABIN & BEHIND THE OFFICER'S SEATING):-</u> Providing and fixing in position low height storage as shown in drg.no. (10) using plywood of required thk. finished with 1mm thick laminate as shown in the drawing and all other sides shall be finished with white enamel paint as detailed there in.The storage units shall be provided with handles (SS-				

Si.No.	Description of work	Qty	Units	Rate	Amount
	finish) as per the approval of the Project consultant / Bank. All exposed plywood surfaces to be finished with 1mm thick laminate of approved make and shade and all exposed edges of plywood to have 1"x 1/4 " TW lipping. shelves with 18mm plywood with enamel paint finish shutter with 18mm thk plywood finished with laminate. All exposed TW sections to be melamined in matching colour laminate and internal surfaces to have white enamel paint as directed. Item to include all necessary Hardware and fittings in SS finish, Godrej multipurpose locks including magnetic ball catch etc. complete in all respects.	27	Sft		
16	<u>WRITING LEDGE :-</u> Providing & fixing writing ledge in the customer area like free standing table of size 2'6" x 1' made of TW frame work & 6mm ply on both sides finished 1mm thick laminate for top & vertical supports & SS pipes as per design.Size: 4' x 1'4".	1	No		
17	<u>VISITORS SEATING (CUSTOMER LOUNGE) :-</u> Featherlite-Orbit Tandem-WT-323-IA3- Three seater with SS arm rest and perforated seating.(3- Nos.)				
		To be supplied by the Bank			
18	<u>NOTICE BOARD</u> Providing notice board 4'0" x 2'6" size in teakwood frame work back with soft board covered with good velvet over 4 mm ma-4 mm marine plywood, front with 4 mm tk. Glass in teakwood frame work, with best quality piano hinges with locking arrangements. All exposed plywood surfaces shall be finished in Ducco Matt.	1	No		
	TOTAL				

Rupees:-

CONTRACTOR'S NAME, SEAL & SIGNATURE