



PROJECT

SCOPE OF WORK: Electrical Installation; Room A

1965 Live Oak Blvd

Yuba City CA 95991

Description of Services.

The contractor agrees to perform all required contracting services related to the exterior painting of the property located at 1965 Live Oak Blvd , Yuba City, Ca 95991

Hours of operation:

Mon thru Friday: 7:00 am to 3:30pm

Saturday: 7:00am to 3:30 pm

The contractor is to provide all supervision, labor (prevailing wage), equipment, tools, supplies and materials to provide the complete electrical installation for the project outlined below.

The proposed work shall include, but shall not necessarily be limited to the following details for project completion:

1. Install (1) surface mount 1 phase panel and feed from existing circuit.
2. All circuits are to correctly fused and protected and all protective devices are properly Identified and coordinated.
3. Extend (2) 20A 120V dedicated circuits to wall via existing under slab raceway or other application.
4. Install all dual channel surface mount metallic raceway, boxes and supports for all electrical circuits.
5. Provide all wire, switches and receptacles.
6. Provide (1) duplex receptacle on each of the (4) walls.
7. Provide path for data cabling from each of (4) walls to hall.
8. The contractor shall provide additional labor, including safety personnel, as required from time to time to comply with Project Schedule at no additional cost to Sutter County
9. All work debris, tools and materials to be cleaned up after each shift to provide clean, safe environment for county staff
10. All electrical equipment shall be maintained in a safe manner during installation. No exposed live circuits shall be accessible to other than qualified personnel.
11. All work shall be performed in strict compliance with all applicable Local and State codes, to include. In addition, all practices shall be in accordance with the latest editions of the NEC of the NFPA, the National Electrical Safety Code, and OSHA.

EXCLUSIONS: Over-time.