THE TOUCH,

PAINTING INC.

SOUTHERN UTAH
3459 Serenity Lane, Santa Clara, UT 84765
Phone: 435-674-2572 Fax: 435-656-5794

..

NORTHERN UTAH
2981 West LeMay Ave., Salt Lake City, Utah 84119
Phone: 801-949-8838 Fax: 801-955-9043

May 6, 2020

To: Virgin Public Works
Attn: Chris Holm
Phone: 435-632-8305
Re: Paint Quote

PRICE QUOTE

We hereby propose to furnish the materials and supply the labor necessary for the completion of painting interior and exterior of Virgin Church, stain all exterior post, facia, soffits and wood side panels on back building and storage canopy located on the grounds of Virgin Church. Prep, prime and paint two restrooms located across the main road from Virgin Church located in Virgin, Utah.

Work Performed: Church Interior: mask and cover all areas not to be painted, patch all holes, caulk all baseboards, windows and door frames as needed, sand walls, base and crown molding, spot prime all repaired areas and repaint one or two coats as needed to cover.
Church Exterior: Pressure wash, mask and cover all areas not to be painted, sand all trim and windows, caulk windows joints and seems as needed, repaint one or two coats as needed to cover.
Exterior stained wood: pressure wash, mask and cover all areas not to be painted, and stain all wood soffits, facia and posts, storage shed wood side panels to receive two coats super deck exterior stain.
Restrooms: pressure wash interior cmu and exterior wood, caulk all joints cracks and seems block fill interior cmu, prime bare wood ceiling with kilz stain blocker sealer and paint interior walls and ceiling with two coats single component epoxy, sand metal doors caulk and paint two coats DTM semi gloss, paint exterior gable ends soffit and facia with two coats 100% acrylic.

Materials Used: Interior Sherwin Williams high primer, Sherwin Williams Promar 200 latex, Sherwin Williams Solo (trim windows and doors), Exterior: Sherwin Williams A-100 100% Acrylic, Sherwin Williams 850A caulk, Rough sawn wood, and wood siding: Super Deck Exterior semitransparent alkyd stain.

Virgin Church, Wood siding and Restroom price quote cont..

Total Cost Labor and Materials:
Church Interior: $2,600.00
Church Exterior: $5875.00
Exterior rough sawn wood and siding back building and storage canopy: $1,950.00
Restrooms interior and exterior: $1395.00

Respectfully submitted,

R. Tim Torres
The Touch Painting Inc. / President